



PEDESTAL POLE



METAL POLE

NOTES:

1. EACH PEDESTRIAN PUSHBUTTON AND PUSHBUTTON SIGN SHALL BE SECURED BY TWO (2) 1/4" - 20 UNC STAINLESS STEEL HEX HEAD BOLTS AND FLAT WASHER DRILLED AND TAPPED INTO THE METAL POLE.
2. THE PEDESTRIAN PUSHBUTTON SHALL HAVE A 1/2" HOLE DRILLED INTO THE METAL POLE FOR WIRING.
3. THE AFFECTED AREA SHALL BE CLEANED WITH METAL WIRE BRUSH AND PAINTED WITH INORGANIC ZINC.

| | | | | | | | | | | | |
|---|---|-----------------------------|--|-----------------|-----------------|-----------------|----------------|---------|---------|---------|---------|
| SPECIFICATION 817 | CATEGORY CODE ITEMS | | | | | | | | | | |
| APPROVED |  DIRECTOR - OFFICE OF TRAFFIC AND SAFETY | | | | | | | | | | |
| SHA State Highway Administration | <table> <tr> <td>APPROVAL • SHA REVISIONS</td><td>APPROVAL • FEDERAL HIGHWAY ADMINISTRATION</td></tr> <tr> <td>APPROVAL 7-1-94</td><td>APPROVAL 7-1-94</td></tr> <tr> <td>REVISED 10-1-01</td><td>REVISED 2-1-01</td></tr> <tr> <td>REVISED</td><td>REVISED</td></tr> <tr> <td>REVISED</td><td>REVISED</td></tr> </table> | APPROVAL • SHA REVISIONS | APPROVAL • FEDERAL HIGHWAY ADMINISTRATION | APPROVAL 7-1-94 | APPROVAL 7-1-94 | REVISED 10-1-01 | REVISED 2-1-01 | REVISED | REVISED | REVISED | REVISED |
| APPROVAL • SHA REVISIONS | APPROVAL • FEDERAL HIGHWAY ADMINISTRATION | | | | | | | | | | |
| APPROVAL 7-1-94 | APPROVAL 7-1-94 | | | | | | | | | | |
| REVISED 10-1-01 | REVISED 2-1-01 | | | | | | | | | | |
| REVISED | REVISED | | | | | | | | | | |
| REVISED | REVISED | | | | | | | | | | |

Maryland Department of Transportation
STATE HIGHWAY ADMINISTRATION
 STANDARDS FOR HIGHWAYS AND INCIDENTAL STRUCTURES

PEDESTRIAN PUSHBUTTON INSTALLATION

STANDARD NO.

MD 817.01